

# **Corrigendum**

**In tender document**  
**Tender Enquiry No. 24/Urology/269(II) 2017-Rish(Admn)**

Dated: 26-11-2017

As per schedule, Pre- Bid meeting of "**Flat Detector based Digital Radiography and Fluoroscopy Urology and Endurology workstation for Department of Urology**" was held on 08-11-2017 at 03.00 PM, in the tender opening room.

After consideration by Store Purchase Committee following modification (deletions/additions/replacements) additions for Tender Enquiry No24/Urology 269(II))/2017-Rish(Admn) has been made.

## **Point srl no. 31 at page no. 06**

**For: -** The equipment installed should be up for 95% of the total warranty time. If the equipment is down for more than 5% suitable action shall be taken against the supplier including imposition of penalty as deemed fit.

**Read as: -** The equipment installed should be up for 95% of the total warranty time. If the equipment is down for more than 5% suitable action shall be taken against the supplier including imposition of penalty as deemed fit. Failure on which penalty will be seven days extended warrantee for each lapsed day.

## **Table**

### **Point Srl No. 02 at page no. 20: -**

**For: -** Table should have minimum lowest height of 90cm or lesser to facilitate easy patient transfer.

**Read as: -** Table should have maximum height of 90 cm or lesser to facilitate easy patient transfer.

### **Point Srl No. 03 at page no. 20: -**

**For: -** System should have motor driven longitudinal and horizontal table top movements. Please specify the range of movements.

**Read as: -** System should have motor driven motorized longitudinal/Imaging Chain and horizontal table top movements. Please specify the range of movements.

### **Point Srl No. 05 at page no. 20: -**

**For: -** Table should have angulations from longitudinal to head down positions (vertical+ 90 degrees to Trendelenburg-20 degrees).

**Read as: -** Table should have angulations from longitudinal to head down positions (vertical +90 degrees to Trendelenburg **-30 degrees) or more**

### **Point Srl No. 06 at page no. 20: -**

**For: -** Table should support patient weight upto 150 kgs.

**Read as:** - Table should support patient weight **at least 150 kgs or more with all the movement.**

**Other Requirement: -**

**Point Srl No. 01 at page no. 22: -**

**For: -** System should have USFDA or European CE approval mandatorily.

**Read as: -** System should have USFDA or European CE **with four-digit registration** approval mandatorily

### **TURNKEY WORK & SCOPE**

**Point Srl No. 01 &2 at page no. 22: -**

**For:-** The Supplier should inspect the proposed site offered by the Consignee Institute in which the DRF system has to be installed and they are required to submit the plan for the complete DRF Centre on a turnkey basis. The scope of work includes complete Civil work, Electrical, plumbing, Furnishing, Air-conditioning and Fire fighting for the construction of DRF Centre.

While preparing the plan, the following aspects have to be addressed.

**Read as: -** Room dimension and room layout where turnkey work is to be done will be provided.

### **ELECTRICAL WORK:**

**Point Srl No. 01 at page no. 22: -**

**For: -** The supply line will be provided by the Institute up to one point within the DRF centre. The distribution panel shall be provided by the vendor. Few lights in each room shall be connected to the UPS to provide emergency lighting.

**Read as; -** The supply line will be provided by the Institute up to one point within the DRF centre. The distribution panel shall be provided by the vendor. Few lights in each room shall be connected to the UPS to provide emergency lighting.

**(5KVA UPS for computers and emergency lighting).**

- **EMD in form of Bank Guarantee is also excepted in this tender.**
- **Delivery Period will be 90 days from the date of opening of Letter of Credit.**

**Note: -** Last date of submission of bids in respect of aforesaid tender is hereby extended till 12-12-2017 at 03:00 PM and Technical bid will be opened on next day at 03.30 PM.