

Corrigendum - 02

Tender No: 04/SE/Civil/2023-24

Name of the work: Supply, installation testing & commissioning of additional 2x10kl Liquid Medical Oxygen (LMO) Tank & allied work at AIIMS Rishikesh.

Sl. No.	Bidder Queries in pre-bid meeting	Condition as per Corrigendum -01	Amended Condition
3	Flow rate of Pressure reducing station (PRS) shall be 10,000 LPM and whether working and standby for PRS to be considered.	<p>“Flow rate of Pressure Reducing Station (PRS) shall be 10,000 LPM. PRS shall be floor mounted type with working capacity of 10,000 LPM and standby arrangement capacity of 10,000 LPM. PRS shall be with all required accessories like safety valve, isolation valves, gauges etc. are included in the scope of work”.</p> <p>The total qty of PRS is 2 nos (1 working + 1 standby).</p>	<p>It is amended that,</p> <p>“Flow rate of Pressure Reducing Station (PRS) shall be with working capacity of 10,000 LPM and Standby capacity of 10,000 LPM. The total quantity of PRS required is 1 (one) number. PRS shall be floor mounted type with all required valves accessories like regulator, safety valve, isolation valves, gauges etc. are included in the scope of work”.</p>

Note:-

1. The above minutes of pre bid meeting shall form part of the tender document and is to be submitted duly signed, stamped and uploaded by the Bidder along with Bid document.
2. All other terms and condition of tender document remains unchanged.